



H - WARD - FIRST FLOOR PLAN

JOINERY DETAILS				
NOTATION	DESCRIPTION	SIZE OF OPENING	SILL	LINTEL
D1	Wooden Door	910 X 2100	-	2100
D2	Toilet Door	750 X 2100	-	2100
W	NCL Window with mesh	1200 X 1800	750	2560

REFERENCE:

PROPOSED SHOWN IN	
EXISTING SHOWN IN	
IV ROD SHOWN IN	
CURTAIN ROD SHOWN IN	
MESH VENTILATOR SHOWN IN	

FINISHING SCHEDULE			
Room Name	Floor Finish	Wall Finish	Ceiling
Corridor	Mosaic floor to be polished	Exi - Wall Tile to be retained & Acrylic Emulsion painting above upto ceiling.	Distemper
Classroom, Nurse changing room, Counseling room, Store room	Mosaic floor to be polished	Acrylic Emulsion painting upto ceiling.	Distemper
Kitchen, Treatment room	Mosaic floor to be polished	Exi - Wall Tile to be retained & Acrylic Emulsion painting above upto ceiling.	Distemper
Sluice, Toilets	Vitrified Tile 300x300mm	Wall Tile upto 2100mm Ht. & Acrylic Emulsion painting above upto ceiling.	Distemper
Beds 1 - 39	Mosaic floor to be polished	Exi - Wall Tile to be retained & Acrylic Emulsion painting above upto ceiling.	Distemper

- NOTES:**
1. All wards to have 1:1 bed to fan ratio and IV rods and hooks to be provided in all beds.
 2. Each bed should have 5 - 5A & 1- 115A electrical points.
 3. Mosaic floor to be polished.
 4. Anti-skid flooring and grab rails to be provided in all toilets.
 5. All damaged ventilator and window mesh to be replaced
 6. All drainage/leakage issues in toilets are to be resolved.
 7. 1 - oxygen point to be provided for bed nos 1-15 & 26-39.
 8. 2- oxygen, 1- suction and 1- Medical gas points to be provided for the bed nos 16 - 20.
 9. Damaged rafters to be repaired.

CHRISTIAN MEDICAL COLLEGE -VELLORE

PROPOSED RENOVATION OF EXISTING H-WARD IN FIRST FLOOR CMC TOWN CAMPUS

H WARD FIRST FLOOR PLAN - (PROPOSED)

CHECKED BY:	DATE : 31.01.2026	PLANNING ENGINEER
DRAWN: YAMUNA	DRG.No : CMC/HW/FF-A002	